

Claim Located Amended August 30, 1919.

Mineral Survey No. 1260

Lot No. N O M E Land District.

**PLAT**  
 OF THE CLAIM OF  
 Nome-Alaska Gold Dredging Company,  
 KNOWN AS THE  
 Croesus Association Placer,

IN N O M E MINING DISTRICT,  
 Territory of Alaska,  
 Containing an Area of 159.992 Acres.  
 Scale of 600 Feet to the inch  
 Variation 19°15'-19°45'E.  
 SURVEYED July 1 - 3, 1920, BY  
 Arthur G. Blake, U.S. Deputy Mineral Surveyor,

The Original Field Notes of the Survey of the Mining Claim of  
 Nome-Alaska Gold Dredging Company,  
 known as the Croesus Association Placer,

From which this plat has been made under my direction,  
 have been examined and approved, and are on file in this Office,  
 and I hereby certify that they furnish such an accurate description  
 of said Mining Claim as will, if incorporated into a patent,  
 serve fully to identify the premises, and that such reference is  
 made therein to natural objects or permanent monuments as  
 will perpetuate and fix the locus thereof.  
 I further certify that Five Hundred Dollars worth of labor has  
 been expended or improvements made upon said Mining Claim  
 by claimant or its grantors and that  
 said improvements consist of 6 or more drill holes,  
 3 cuts, and 1 pit. Total value \$880.00,

that the location of said improvements is correctly shown  
 upon this plat, and that no portion of said labor or improve-  
 ments has been included in the estimate of expenditures  
 upon any other claim.  
 And I further certify that this is a correct plat of said Mining  
 Claim made in conformity with said original field notes of the  
 survey thereof, and the same is hereby approved.

U.S. Surveyor General's Office. *A. G. Dummer*  
 Juneau, Alaska, U.S. Surveyor General.  
 September 15, 1920. ALASKA.

MINERAL SURVEY No. 1260

LOT No. ....

RECEIVED  
SUR. GEN. OFFICE

AUG 5 1920

ANSWERED

Nome Land District.

FIELD NOTES

OF THE SURVEY OF THE MINING CLAIM OF

Nome-Alaska Gold Dredging Company,

KNOWN AS THE

Business Association Placer

Cape Nome Recording Precinct and Mining District,  
Territory of Alaska County,

Section, Township, Range

Surveyed under instructions dated Oct. 21<sup>st</sup>, 1920

by Arthur H. Blake

U. S. Mineral Surveyor.

Claim located July 31<sup>st</sup>, 1906

Survey commenced July 1<sup>st</sup>, 1920

Survey completed July 3<sup>rd</sup>, 1920

Address of claimant .....

DATES OF AMENDED LOCATIONS.

Aug. 30<sup>th</sup> 1919

Address of authorized agent  
Edmund Reed  
Nome - Alaska.

FIELD NOTES - MINERAL SURVEY NO. 1260

Feet

CENSUS ASSOCIATION PLAT

Beginning at Cor. 1 identical with Cor. 1 Sea Horse <sup>Association</sup> plat-  
 cer, Sur. No. 1162, a schist stone 12ins. above ground marked  
 1, S.H.-1162, with earth mound alongside of same.

I mark this cor. 1, C.-1260 for Cor. 1 this survey.

U.S.L.M. <sup>No</sup> Sur. 1162 bears S. 35° 25' E. 1868.2ft.

No other bearings available.

THENCE S. 42° 54' E.

Var. 19° 25' E.

636.0 Center Melbourne Creek, 10ft. wide, course S.W.

3555.0 To Cor. 2, identical with loc. A granite boulder 12ins. x 24  
 ins. 6ins. above ground. I mark same 2, C.-1260 and cross (x)  
 on top for true point and erect earth mound 30ins. base  
 24ins. high on E. side of cor.

No bearings available.

THENCE S. 77° 08' E.

Var. 19° 45' E.

860.0 Center creek 3ft. wide, course southerly,

1427.0 Center creek 6ft. wide, course southerly,

1557.0 Left bank Cripple River, course easterly,

2088.0 " " " " southeasterly,

2516.0 To Cor. 3, identical with loc. A schist boulder 16ins. x  
 48ins. 4ins. above surface. I mark same 3, C.-1260 and cross  
 (x) on top for true point and erect earth mound 30ins. base  
 24ins. high east side of cor. No bearings available.

THENCE S. 52° 50' E.

Var. 19° 40' E.

1164.0 To Cor. 4 identical with loc. A limestone boulder,  
 24ins. x 36ins. 6ins. above surface. I mark this stone 4, C.-  
 1260 and cross (x) on top for true point and erect earth  
 mound 30ins. base 24ins. high E. side of same.

No bearings available for cor.

THENCE S. 37° 10' W.

Var. 19° 40' E.

325.0 Left bank Cripple River, course S.E.

440.0 Right bank of same, " S.E.

FIELD NOTES - MINERAL SURVEY NO. 1260

Feet  
 455.0 Center ditch 8ft. wide, course S.E.  
 744.4 To Cor. 5, identical with loc. for which I set a limestone  
 24x8x6ins. 14ins. in ground, marked 5, C.-1260 and cross (x)  
 on top for true point and erect earth mound 30ins. base  
 24ins. high west side of same. No bearings available.

THENCE N. 46° 41' W.

Var. 19° 40' E.

1072.7 To Cor. 6 identical with loc. A limestone boulder  
 48ins. x 8ins. 12ins. above surface. I mark same 6, C.-1260,  
 and cross (x) on top for true point and erect stone mound  
 30ins. base 24ins. high west side of cor.

No bearings available.

THENCE N. 87° 53' W.

Var. 19° 30' E.

2457.0 To Cor. 7 identical with loc.

This cor. being on low inundated ground and liable to destruc-  
 tion, I mark a Witness Corner, 7, C.-1260, W.C. on limestone boul-  
 der 8x4ft. 4ft. above surface, which bears S. 16° 14' W. 5ft. from  
 true corner. Cor. 3 this survey bears N. 16° 14' E. 1077.1ft.

THENCE N. 46° 23' W.

Var. 19° 15' E.

From True Corner 7, C.-1260,

4319.0 To Cor. 8, identical with location and with Cor. 3 Sea Horse  
*Association*  
 Placer Sur. 1162, a granite stone 12ins. above ground with  
 earth mound alongside, and marked 8, S.H.-1162.

I mark this stone 8, C.-1260 for Cor. 8 this survey.

No bearings available.

THENCE N. 56° 51' E.

Var. 19° 30' E.

Along line 2-1, Sea Horse *Association* Placer, Sur, 1162,

930.0 Right bank Cripple River, course southeasterly,  
 1015.0 Left bank of same, course southeasterly,  
 1200.0 To Cor. 1 and place of beginning.

Containing an area of 159.992 acres.

L O C A T I O N

This claim is on unsurveyed ground and situate on

## FIELD NOTES - MINERAL SURVEY NO. 1260

Cripple River, about 16 miles northwesterly from Nome and five miles north of the shore of Bering Sea, in the Cape Nome Recording Precinct Territory of Alaska.

## EXPENDITURE OF \$500.00

I certify that the value of the labor and improvements done and made on this claim by the claimant or its grantors for its benefit and development, is not less than five hundred dollars and that said improvements consist of open cuts and drill holes as follows:

	From Sta. 462 on line 8-1	
No. 1-	Drill hole deep, bears S. 9° 34' E. 531ft.	Value \$ 100.00
" 2-	" " " bears S. 89° 49' E. 225 "	" " \$ 100.00
	From U.S.L.M. No. 1162	
" 3-	Cut 42x9x3ft. deep, Course west, E. end bears N. 63° 30' W. 414ft.	
		Value \$60.00
" 4-	Cut 168x3x3ft. Course N.W. South end bears N. 64° 30' W. 256ft.	
		Value \$90.00
" 5-	Cut 75 x 8 x 3ft. deep, Course S.W. North end bears S. 40° W. 75ft.	Value \$ 120.00
" 6-	Pit 6 x 8 x 4ft. deep, bears S. 44° 30' E. 532ft.	Val. \$ 10.00
" 7-	Other scattered surface work, not located being under snow,	
" 8-	Three 6in. drill holes near line 8-1, not located,	Val. 300.00
" 9,	----- holes made by hand drill near center of claim, not located,	Val. \$100.00
		<u>Total value \$ 880.00</u>

NOTE: Information regarding items Nos. 8 and 9, furnished by affidavits accompanying these notes.

## OTHER IMPROVEMENTS

A frame mess house 20 ft. square, 2 story, the SW. Cor. bears N. 5° 30' E. 12 ft. from U.S.L.M. No. 1162, Course of side S 44° 30' W.

FIELD NOTES - MINERAL SURVEY NO. 1260

I N S T R U M E N T

This survey was made with a Bausch & Lomb mining transit equipped with vertical circle and solar eyepiece and reading to single minutes. Number on instrument No. 7932.

The courses of this survey were deflected from the true meridian, as determined by direct solar observation, July 2nd, 1920, 10 a.m. at sta. 1230 on line 1-2, and verified by angular connection with line 1-2 of Sur. 1162.

The distances were measured with a 100ft. steel tape of standard manufacture with plumb bobs used on sloping and brushy ground.

U. S. LOCATION MONUMENT

U.S.L.M. <sup>No</sup> Sur. 1162 to which this claim is tied, is a limestone about 8ft. sq. 4ft. above ground, marked U.S.L.M. 1162 and cross (x) on top surface, situate about 200ft. east of channel of Cripple River in Lat. 64° 37.5' N. Long. 165° 51.5' W.

R E M A R K S

The survey of this claim is identical with its location on the ground and the disagreement between these field notes and the certificate of location with regard to the courses and lengths of the boundary lines, is due to errors in the latter.

The adjoining claims are, on the north the Sea Horse placer Sur. 1162 owned by claimant herein, on the east, south and west unsurveyed and names of claims and claimants unknown.

NOTE: The Witness Corner to Cor. 7 herein I set outside the lines of claim on account of low marshy inundated ground on lines 6-7-8, and extending considerable distance both ways from cor.

NOTE: I find the course to U.S.L.M. <sup>No</sup> Sur. 1162 from Cor. 1-1162 as given in the notes of that survey (S. 34° 11' E.) to be in error. The true course and distance being S. 35° 25' E. 1262.2ft.

**Directions:**—1. Carry out the area in acres to three decimals, and all other calculations to two decimals only.  
 2. In balancing Lat. and Dep. do not obliterate or change the original figures.  
 Put the corrected figure or figures above in red ink. Do not change the footing of the original figures.  
 The corrections for balancing fallings should be proportional to the lengths of the lines.  
 3. In calculations of fallings take result to nearest hundredth. In calculations of N. and S. areas drop all after second decimal. Surveyors are advised to use the Standard Field Tables issued by G. L. O.

**TABLING AND CALCULATIONS OF**

*Quarry Description Place*

*July 1260*

No.	COURSE	DISTANCE	LATITUDES		DEPARTURES		DOUBLE M. D.	N. AREAS	S. AREAS
			NORTH	SOUTH	EAST	WEST			
8	N. 56° 51' E.	1700. —	656.20 <sup>07</sup>		1004.69 <sup>57</sup>		1004.78	659266.01	
1	S. 42° 54' E.	3555. —		2604.18 <sup>54</sup>	2419.96 <sup>20</sup>		4429.79		11537698.14
2	S. 77° 08' E.	7516. —		560.26 <sup>54</sup>	2452.82 <sup>35</sup>		9303.03		521472044
3	S. 52° 50' E.	1164. —		703.22 <sup>35</sup>	727.57 <sup>66</sup>		12683.70		8921080.40
4	S. 37° 10' W.	744.4		693.20 <sup>8</sup>			449.22 <sup>66</sup>	13161.70	7808573.38
5	N. 46° 41' N.	1092.7	735.40 <sup>78</sup>				780.46 <sup>78</sup>	11931.66	8774076.79
6	N. 87° 52' W.	2451.7	98.15 <sup>04</sup>				2449.31 <sup>04</sup>	8702.15	791721.61
7	N. 46° 23' W.	4319. —	2979.38 <sup>88</sup>				3126.83 <sup>88</sup>	3126.51	9313591.90
			4462.73	4460.86	6805.04	6806.32		19543596.81	133482072.36
			1.74	1.74	5.68	5.68		19543596.81	

87120 / 13938476.05 (159.992)

Area 159.992 Acres

# FINAL OATHS FOR SURVEYS.

## LIST OF NAMES.

A list of the names of the individuals employed by Arthur G. Blake  
 United States Mineral Surveyor, to assist in running, measuring, and marking the lines, corners, and  
 boundaries described in the foregoing field notes of the survey of the mining claim of  
The Nome-Muskeg Gold Dredging Company  
 known as the Brosius association placer  
 and showing the respective capacities in which they acted.

Taylor Payne . . . . . Chairman.

. . . . . Chairman.

. . . . . Assman.

William Heitman . . . . . Flagman.

## FINAL OATHS OF ASSISTANTS.

We, Taylor Payne and William Heitman  
 and Arthur G. Blake, do solemnly swear that we assisted Arthur G. Blake  
 United States Mineral Surveyor, in marking the corners and surveying  
 the boundaries of the mining claim of The Nome-Muskeg Gold Dred-  
ging Company,  
 known as the Brosius association placer,

represented in the foregoing field notes as having been surveyed by said mineral surveyor and under his  
 direction; and that said survey has been in all respects, to the best of our knowledge and belief, faithfully  
 and correctly executed, and the corner and boundary monuments established according to law and the instruc-  
 tions furnished by the United States Surveyor-General for the Territory of Alaska.

Taylor Payne . . . . . Chairman.

. . . . . Chairman.

. . . . . Assman.

William Heitman . . . . . Flagman.

Subscribed and sworn to by the above-named persons before me this seeth

day of July, 1920

Chas. Evans  
Notary Public

My commission expires Sept 18, 1923



## FINAL OATH OF U. S. MINERAL SURVEYOR.

I, Arthur G. Blake, U. S. Mineral Surveyor,  
do solemnly swear that, in pursuance of instructions received from the United States  
Surveyor General for the Territory of Alaska, dated  
Oct. 21-1919, I have, in strict conformity to the laws of the  
United States, the official regulations and instructions thereunder, and the instructions  
of said Surveyor General, faithfully and correctly executed the survey of the Mining  
Claim of The Nome - Alaska Gold Dredging Com-  
pany, known as the  
Excelsior Association Place  
situate in Nome Recording Precinct Mining District,  
Territory of Alaska County, \_\_\_\_\_ in Section  
\_\_\_\_\_, Township No. \_\_\_\_\_ Range No. \_\_\_\_\_,  
and designated as Survey No. 1260, as represented  
in the foregoing field notes, which accurately show the boundaries of said mining claim  
as distinctly marked by monuments on the ground, and described in the attached copy  
of the location certificate, which was received by me from the Surveyor General with  
said instructions, and that all the corners of said survey have been established and per-  
petuated in strict accordance with the law, official regulations and instructions there-  
under; and I do further solemnly swear that the foregoing are the true and original  
field notes of said survey and my report therein, and that the labor expended and  
improvements made upon said mining claim by claimant or its grantors  
are as therein fully stated, and that the character, extent, location, and itemized value  
thereof are specified therein with particularity and full detail, and that no portion of  
said labor or improvements so credited to this claim has been included in the estimate  
of expenditures upon any other claim.

Arthur G. Blake  
U. S. Mineral Surveyor.

Subscribed and sworn to by the said  
U. S. Mineral Surveyor, before me

Mary Patti  
day of July, 1920

Arthur G. Blake  
I am Notary,  
this 12

Mary Patti  
Notary Public in and for the Territory of Alaska  
My Commission Expires 1<sup>st</sup> September 1922.

SURVEYOR GENERAL'S CERTIFICATE OF APPROVAL OF FIELD NOTES  
AND SURVEY OF MINING CLAIM

DEPARTMENT OF THE INTERIOR  
OFFICE OF U. S. SURVEYOR GENERAL

Juneau, Alaska,

September 15, 1920. ~~=====  
=====~~

I, U. S. Surveyor General for Alaska

do hereby certify that the foregoing and hereto attached Field Notes and Return of the Survey of the Mining Claim of Nome Alaska Gold Dredging Company,

known as the Croesus Association Placer

situate in Nome mining district,


Nome, Territory of Alaska,

in Section \_\_\_\_\_, Township No. \_\_\_\_\_, Range No. \_\_\_\_\_,

designated as Survey No. 1260

executed by Arthur G. Blake, U. S. Mineral Surveyor,

July 1 - 3, 1920, under my instructions dated October 21, 1919, have been critically examined and the necessary corrections and explanations made, and the said Field Notes and Return, and the Survey they describe, are hereby approved. The certified copy of the location certificate filed by the applicant for survey is on file in this office and a true copy of said certified copy of said location certificate is included and made a part of the transcript of the field notes.



U. S. Surveyor General for Alaska.

MINERAL SURVEY NO. 1260

R E P O R T

A The soil of this claim is principally gravel, clay and alluvium excepting the channel proper of Cripple River, from which all surface soil has been washed away, leaving bare gravel only.

The surface of the claim supports a growth of moss, <sup>and</sup> grass with patches of scrub willows on the banks of the river.

B The principal stream on this claim is Cripple River which flows southeasterly therein and the full length of same.

Melbourne Creek a small stream about 10ft. wide flows into claim near its N.E. corner.

Two other smaller streams flow southerly into the claim on its east side about midway of its length.

A frame mess house 20ft. sq. two story, the S.W. cor. bears N. 5° 30' E. 12ft. from U.S.L.M. <sup>N<sup>o</sup></sup> 1162, Course of side S. 44° 30' W.

C The workings on this claim consist of:

From sta. 462 on line 8-1

- 1- Drill hole, 6in. dia. deep, bears S. 9° 34' E. 531ft.
- 2- " " 6 " " " " S. 89° 49' E. 225ft.

From U.S.L.M. <sup>N<sup>o</sup></sup> 1162

- 3- Cut 42x9x3ft. deep, course west, E. end bears N. 63° 30' W. 414ft.
- 4- Cut 168x3x3ft. course N.W. South end bears N. 64° 30' W. 256ft.
- 5- Cut 75x8x3ft. deep, course S.W. N. end " S. 40° W. 75ft.
- 6- Pit 6x2x4ft. deep, bears S. 44° 30' E. 532ft.
- 7- Other scattered surface work, not located, being under snow,
- 8- Three 6in. drill holes near line 8-1, not located,
- 9- ----- holes made by hand drill near center of claim.

D The nearest post office to the claim is Nome a mining town of about 1000 population, situate on the shore of Bering Sea at the mouth of Snake River and distant about 16 miles southeasterly from claim. Nome is also the nearest railroad station being the terminus of the Nome-Arctic Railroad.

This railroad is not at present in operation.

E There are no known lodes or systems of lode deposits in the vicinity or on the claim.

MINERAL SURVEY NO. 1200

F. This claim is well adapted for dredge mining or for the use of hydraulic elevators, the gold bearing part of the claim being unfrozen gravel of sufficient depth and a plentiful supply of water for mining purposes can be obtained from Cripple River which flows through the claim.

G. The workings and expenditures on the claim, done and made by the claimant or its grantors for its development, consist of all the items mentioned under paragraph C of this report.

H. There are no mines, salt licks, salt springs or mill seats on the claim nor any timber and there are no known hot springs or medicinal springs on the claim or within one half mile of same.

*Arthur G. Blake*

U.S. Mineral Surveyor.

UNITED STATES OF AMERICA

TERRITORY OF ALASKA

SECOND DIVISION. . . . ss:

A. F. McIntosh, being duly sworn,  
deposes and says:

That he is a miner by occupation  
and is well acquainted with the Croesus Claim, situate on Cripple  
River, in the Cape Nome Recording Precinct, Territory of Alaska.

That during year 1913, the fol-  
lowing work was done by other and himself for the benefit of said  
claim, viz.:

Five (5) drill holes, commencing at the  
upper northeast corner of claim and extending in a  
westerly direction across claim, said holes being  
25, 24, 22, 20 and 16 feet deep, and totalling  
108 feet.

That a Keystone Power Drill with  
6" casing, was used in connection with the drilling of the  
property and that the value of the work was Five Hundred &  
00/100 (\$500.00) dollars, or over.

That in the year 1914, affiant  
assisted A. J. Jarmuth and others and drilled holes in the  
center north half of claim, with a hand drill, and that the  
value of the work was One hundred and 00/100 (\$100.00) dollars,  
or over.

That all work above enumerated was  
done for the benefit of the Croesus Claim.

A. F. McIntosh

Subscribed and sworn to before me this 13<sup>th</sup> day of July, 1920.

*Clayton, Clerk*

*Notary Public*

*My commission expires Sept. 15, 1920*

UNITED STATES OF AMERICA  
TERRITORY OF ALASKA  
SECOND DIVISION. . . . ss:

E. R. Jordan, being duly sworn,  
deposes and says:

That he is well acquainted with  
the Croesus Claim, situate on Cripple River in the Cape Nome  
Recording Precinct, Territory of Alaska.

That during the year 1913, affiant  
paid over one thousand (\$1,000.) dollars for drilling several  
holes in the Croesus Claim, said holes being drilled as fol-  
lows:

Five (5) drill holes, 26, 24, 22, 20 and  
16 feet, respectively, drilled with 6"  
casing, commencing at the upper northeast  
corner of claim and extending in a westerly  
direction across said claim.

That a Keystone Power Drill  
was used in connection with said drilling and that the  
work was done for the benefit of the Croesus Claim.

E. R. Jordan

Subscribed and sworn to before  
me this 13<sup>th</sup> day of July, 1920.

*Clarence C. Coker*  
*Notary Public*  
*City of Nome, Alaska*

# OATH OF UNITED STATES MINERAL SURVEYOR

Under paragraph 60, General Mining Circular, approved May 21, 1907.

I, Arthur G. Blake, U. S. Mineral Surveyor,  
do solemnly swear that in pursuance of an order received from the U. S. Surveyor  
General for Alaska, dated Oct 21, 1919,  
I have made, under the provisions of paragraph 60, General Mining Circular, approved  
May 21, 1907, a personal and thorough examination, upon the premises, of the placer  
mining claim of The Nome - Alaska Gold Dredging Com-  
pany  
known as the Process Association Placer,  
situate in Cape Nome Recording Precinct, Mining District,  
Territory of County, Alaska, embracing

~~in Township No~~                     , ~~Range No~~                     , and that my report  
of such examination, hereto attached, is specific and in detail, and is a full and true  
statement of the facts upon all the points specified in the paragraph referred to.

Arthur G. Blake  
U. S. Mineral Surveyor.

Subscribed and sworn to by the said Arthur G.  
Blake, U. S. Mineral Surveyor,  
before me J. W. M. Street  
this 15<sup>th</sup> day of July, 1920

J. W. M. Street  
Notary Public in and for the Territory of Alaska  
my commission expires 1<sup>st</sup> December 1922

CORROBORATIVE AFFIDAVIT UNDER PARAGRAPH 60, GENERAL MINING CIRCULAR.

APPROVED MAY 21, 1907.

United States of America  
County of Territory of Alaska

Taylor Payne and William Heitman

being first duly sworn, severally depose and say that he is personally and well acquainted with the placer-mining claim of

The Home Alaska Gold Dredging Company,  
known as the Heards Association

Placer, situate in

Lape Home Pending Mining District,  
Territory of Coatsy, Alaska, embracing

Range No. \_\_\_\_\_, in Township No. \_\_\_\_\_

; and also with the character of all the land included in said claim, and has been so acquainted for \_\_\_\_\_ years last past; that his knowledge of said claim and land is derived from personal examination of same,

and is such as to enable him to testify understandingly with regard thereto; that he has carefully read the foregoing report of William G. Blake, U. S. Mineral Surveyor, and that to his own personal knowledge said report is in all respects true and accurate.

Taylor Payne  
William Heitman

Subscribed and sworn to by the above-named persons before me this sixth day of July, 1920.

Charles C. Evans  
Notary Public

My commission expires Sept. 15 '1923



U. S. SURVEYOR GENERAL'S APPROVAL  
OF  
REPORT UNDER PARAGRAPH 167, GENERAL MINING CIRCULAR.  
APPROVED MARCH 29, 1909.

DEPARTMENT OF THE INTERIOR,  
OFFICE OF U. S. SURVEYOR GENERAL.

Juneau, Alaska,

September 15, 1920.


I, R. J. Sommers, U. S. Surveyor General for Alaska

do hereby certify that the foregoing and annexed report of the examination of the placer mining claim of  
Nome Alaska Gold Dredging Company,

known as the  
Crossus Association Placer,

made by U. S. Mineral Surveyor Arthur G. Blake,

under the provisions of paragraph 167 of General Mining Circular, approved March 29, 1909, and under  
my instructions dated October 21, 1919, has been carefully examined  
and conforms in all respects to the requirements of said paragraph; and said Report is hereby approved.



U. S. Surveyor General for Alaska.