

# ANCSA 17(b) Easements



Access Law and Issues Affecting Public and Private Lands In Alaska February 26, 2016

Rick Elliot, SR/WA

10. **It's the law.** It is a federal law, part of the Alaska Native Claims Settlement Act (ANCSA) 1971, Section 17(b) (1) (2) and (3). ( P.L. 92-203-85 Stat. 688). Federal regulation 43CFR 2650.47 describes the guidelines used in reserving easements in conveyance documents. 17(b) easements apply only to land conveyed under ANCSA. Does not apply to Native allotments or other private land conveyed under another authority.



Rick Elliot, SR/WA

8. Reserves easements across Native corporation land for ACCESS to public lands or major waterways.

Easements are to be minimal and non-duplicative.

Rick Elliot, SR/WA

7. Easement use is limited and very specific and is described in the conveyance document issued to a Native corporation.

Any other use other than what is described in the conveyance document is not authorized.

# Top 10 Things About ANCSA 17(b) Easements Rick Elliot, SR/WA

6. No scenic easements, no recreational easements, no hunting and fishing easements as 17(b) easements.

(These activities cannot occur on the easement itself but the easement can provide access to those areas on public lands and waters where they can view, recreate, and hunt and fish.)

Rick Elliot, SR/WA

5. 17(b) easements do not appear on BLM master title plats, but you can research through the BLM website.

Also, the maps are not recorded with the conveyance document.

Rick Elliot, SR/WA

4. Management and marking of 17(b) easements is discretionary and may be limited because of funding and/or availability of personnel.

BLM gives high priority to easements with high use, the potential for conflict, or have known safety hazards.

# Top 10 Things About ANCSA 17(b) Easements Rick Elliot, SR/WA

3. 17(b) easements can be terminated but a public process in required. BLM is the responsible agency.

The easements may be terminated for the following reasons:

- non use by the public
- easements that are topographically unfeasible
- easements which do not meet existing criteria
- easements that are no longer needed.

# Top 10 Things About ANCSA 17(b) Easements Rick Elliot, SR/WA

2. Trespass can be an issue related to 17(b) easements.

Trespass must be separated into 2 categories to reflect respective management authority and responsibility. Any trespass that interferes with public use of the easement is a Federal responsibility. Any trespass that impact resources or does not interfere with public use is the responsibility of the servient land owner.

Rick Elliot, SR/WA

- 1. Concerns are many from and different perspectives: government (as easement holder); Native corporations (as land owners) and the public (easement user). Following are some of the concerns:
- Protection of public right of access to public lands
- Liability resulting from public use
- Effective and efficient land management; both public and private land
- Trespass on private land and protection of resources from theft, damage and fire
- Concentration of users on public land by the limited access opportunities
- Documentation of use to preserve the easement reservation
- Termination of unused or unfeasible easements
- Public Safety



Search BLM

Go

#### SDMS

Home

ACRES

Map Interface

Conveyance Documents

Master Title Plats

**Survey Plats** 

ANCSA 17(b) Easements

Alaska Public Law Documents

Download Data

Tools and Utilities

WMS

News

**Data Updates** 

FAO

Feedback

Spatial Data Management System

Welcome to the Bureau of Land Management's Spatial Data Management System website. The SDMS website provides access to on-line BLM-Alaska land record documents, reports and GIS data.

#### Alaska Case Reporting Enterprise System

The ACRES reports contain BLM Alaska case information. Reports include native, state and private land conveyance cases, as well as, leases, permits, federal mining claims, easements and more.

#### SDMS Land & Resources Map Interface



Interactive map interface portraying lands and natural resources information in Alaska. Provides data download services, access to land parcel data, documents and case reports. Data streaming service available.

#### Conveyance Documents

Scanned images of BLM Alaska land conveyance documents including: Patents, Tentative Agreements and Interim Conveyances Issued since 1965.

#### **Master Title Plats**

Scanned images of BLM Alaska MTPs. These maps portray the Bureau's record of current federal land ownership and land status.

#### Survey Plate

Scanned images of Cadastral land survey plats and field notes.

#### ANCSA 17(b) Easement Maps

Scanned images of federal easements across native lands, presented on USGS quadrangles.

#### Alaska Public Laws, Orders and Directives Online

Scanned Images of federal Alaska Public Laws, Orders and Directives

Please note that the on-line data and documents available through this site do not constitute nor replace official legal records, documents or case files. Refer to specific records on file at BLM for official record information.

Please review Disclaimer and Privacy Policy for terms and conditions for use of this site.

USA.GOV | No Fear Act | DOI | Disclaimer | About BLM | Notices | Get Adobe Readen® Privacy Policy | FOIA | Kids Policy | Contact Us | Accessibility | Site Map | Home

February 26, 2016

http://sdms.ak.blm.gov

#### Sec. 17(b) Easements Online DjVu format:

--- Select an Easement Map ---


#### Download PDF format:

--- Select an Easement Map ---


Download PDF

Enter the first letter of the name of the desired quadrangle map. Click the desired map from the dropdown menu.

Note: The DjVu format requires that you have the **DjVu** plugin installed for your browser.




http://sdms.ak.blm.gov/scanned\_images/esmtindex.html



http://sdms.ak.blm.gov/scanned\_images/esmtindex.html

# Easement Identification Numbers (EIN) Sponsor Codes



C5

### EASEMENT SPONSOR CODE

7	Alaska Center	for the	Environment
3	Department of	Defense	

C Department of Interior:

31 Bureau of Outdoor Recreation

C2 National Park Service

3 Bureau of Mines

C4 BLM State Office

BLM District Office

C6 Fish and Wildlife

C7 Geological Survey

C8 Alaska Power Administration

D State of Alaska:

D1 Division of Lands

D2 Division of Parks

D3 Department of Highways

D4 Division of Planning and Research

Division of Aviation

D6 Division of Public Works

Department of Fish and Game

E Land Use Planning Commission

F RCA Alaska Communications

G U.S. Forest Service

H The Alaska Railroad

I Federal Aviation Administration

J U.S. Coast Guard

K Corps of Engineers

L General Public

M Village Corporation

Regional Corporation

February 26, 2016

Search

#### Alaska

- **What We Do**
- E Visit Us
- **⊞** Information Center
- **⊞** Get Involved
- **⊞** Our Offices/Centers

Contact Us Directory Email Us BLM>Alaska>Programs>Lands and Realty>17b Easements

#### Section 17(b) easement general information

17(b) easements<sup>1</sup> are rights reserved to the United States. They take the form of 60-foot wide roads, 25- and 50-foot trails, and one-acre sites for short-term uses. These rights are reserved<sup>2</sup> when the BLM conveys land to a Native corporation under the Alaska Native Claims Settlement Act (ANCSA). There are no 17 (b) easements across public lands.

#### What is the purpose of 17(b) easements?

Most 17(b) easements are reserved to allow the public to cross private property to reach public lands<sup>3</sup> and major waterways. Using 17(b) easements does not allow the public to use the private lands these easements cross. It is very similar to the street in front of many homes. The public has the right to travel on the street, but

they do not have the right to dump litter on private property or trespass on private lawns.

#### Notes:

1 17(b) easements may also be reserved to and from communities, airports, docks, marine coastline, groups of private holdings sufficient in number to constitute public use and government facilities. See 43 Code of Federal Regulation (CFR) 2650.4-7 for a complete listing of the types of public easements.

How are 17(b) easements identified and reserved?

200000

Print Page

17(b) easement General Information

What can I do on 17(b) easements?

More Information

Seldovia 17b easement

#### General Legal Authorities & Agreements

- Section 17(b) of the Alaska Native Claims Settlement Act (ANCSA) of December 18, 1971, 43 U.S.C. 1616 (1b) (authority for reserving public easements)
- Federal Land Management Policy Act of 1976 (FLPMA)
- Section 903 (a) and (b) of the Alaska National Interest Lands Conservation Act (ANILCA) of December 2. 1980, (adds guiding principles when reserving easements and authorizes the acquisition of easements)

How are 17(b) easements identified and res

http://www.blm.gov/ak/st/en/prog/lands\_realty/17b\_easements.html

 $<sup>^2</sup>$  The authorities for reserving 17(b) easements are the Alaska Native Claims Settlement Act, 43 U.S.C. 1616(b) and 43 Code of Federal Regulation (CFR) 2650.4-7.

<sup>&</sup>lt;sup>3</sup> Publicly owned land means all Federal, State, or municipal and borough lands or interests and submerged lands as defined by the Submerged Lands Act. This definition of public lands also includes lands selected by, but not conveyed to, a Native corporation.

Search

What can I do on a 17(b) easement?

BLM>Alaska>Programs>Lands and Realty>17b Easements>What can I do?

17(b) Easement General

Print Page

Information
What can I do on 17(b)
easements?

More Information

Seldovia 17b easement

#### General Legal Authorities & Agreements

- Section 17(b) of the Alaska Native Claims Settlement Act (ANCSA) of December 18, 1971, 43 U.S.C. 1616 (1b) (authority for reserving public easements)
- Federal Land Management Policy Act of 1976 (FLPMA)
- Section 903 (a) and (b) of the Alaska National Interest Lands Conservation Act (ANILCA) of December 2. 1980, (adds guiding principles when reserving easements and authorizes the acquisition of easements)
- Code of Federal Regulations 43 CFR 2650.4-7 and 2650.0-5 (public easements)
- Code of Federal Regulations 43 CFR 4.410 (who can appeal)
- Departmental Manual
   601 DM 4 (Department

#### Alaska

- **⊞** What We Do
- **■** Visit Us
- **Information Center**
- **⊞** Get Involved
- Our Offices/Centers

Contact Us Directory

**Email Us** 

The uses allowed on a 17(b) easement are limited, and they are described in the conveyance document issued to a Native corporation. Common allowable uses for most 17 (b) easements are described below. Any use other than what is described in the conveyance document is not authorized. Please check with the agency managing the easement or the owner of the land it crosses if authorized uses are not posted at the trailhead or site easement.

An example of authorized use is: motorized vehicles on 25-foot-wide trails are generally limited to snowmobiles, two- and three-wheeled vehicles, and all-terrain vehicles having less than 3,000 lbs. gross weight. Larger vehicles are not authorized on a 25-foot public easement, even if the physical condition of the trail would support the use. An easement may also be limited to seasonal use. The land owner is not bound by these restrictions.

#### Common Allowable Uses

**25-Foot Trail**— The uses allowed on a 25-foot-wide trail easement are travel by: foot, dogsleds, animals, snowmobiles, two- and three-wheeled off-highway vehicles; and small all-terrain vehicles (less than 3,000 lbs, gross vehicle weight).

**50-Foot Trail**— The uses allowed on a 50-foot-wide trail easement are those allowed for a 25-foot trail plus large all-terrain vehicles (more than 3,000 lbs. gross vehicle weight), tracked vehicles, and four-wheel-drive vehicles.

**60-Foot Road**— The uses allowed on a 60-foot-wide road easement are those allowed for 25- and 50-foot trails plus automobiles and trucks.

1-Acre Site— The uses allowed on a site easement are: vehicle parking (such as aircraft, boats, all-terrain vehicles, snowmobiles, cars, and trucks), temporary camping, and loading or unloading. Temporary camping and loading or unloading is limited to 24 hours.

#### Can I hunt, fish, or trap on or from a 17(b) easement?

No. Hunting, fishing, or trapping on or from the easement are never allowed, unless you obtain a permit from the landowner for this purpose.

February 26, 2016

http://www.blm.gov/ak/st/en/prog/lands\_realty/17b\_easements/ allowable \_uses.html



Search

#### Alaska

- What We Do
- Visit Us
- **⊞** Information Center
- **⊞** Get Involved
- **⊞** Our Offices/Centers

Contact Us Directory Email Us BLM>Alaska>Programs>Lands and Realty>17b Easements>More Info

#### Where can I find information on 17(b) easements?



Download Black and White 17(b) Easement brochure- 2.2 MB

Download Color 17(b) Easement brochure- 2.9 MB

#### Federal Land Agencies

Fairbanks District Office

Alask a State Office (907) 271-5960
Anchorage District Office
Anchorage Field Office (907) 267-1246
Glennallen Field Office (907) 822-3217

#### **US Fish and Wildlife Service**

Anchorage Div. of Realty and Natural Resources (907) 786-3490

(907) 474-2251

http://alaska.fws.gov/nwr/realty/map/easements.htm

National Park Service www.nps.gov/state/ak Alaska Regional Office (907) 644-3427

#### State of Alaska Agencies

**Dept. of Fish and Game** www Anchorage Office (907)

www.adfg.state.ak.us (907) 267-2463

Dept. of Natural Resources

Anchorage Office Fairbanks Office www.dnr.state.ak.us (907) 269-8400 (907) 451-2705 Print Page

17 (b) easement General Information

What can I do on 17(b) easements?

More Information
Seldovia 17b easement

#### General Legal Authorities & Agreements

- Section 17(b) of the Alaska Native Claims Settlement Act (ANCSA) of December 18, 1971, 43 U.S.C. 1616 (1b) (authority for reserving public easements)
- Federal Land Management Policy Act of 1976 (FLPMA)
- Section 903 (a) and (b) of the Alaska National Interest Lands Conservation Act (ANILCA) of December 2. 1980, (adds guiding principles when reserving easements and authorizes the acquisition of

http://www.blm.gov/ak/st/en/prog/lands\_realty/17b\_easements more\_info.html

## BLM ANCSA 17(b) Easement Brochure



17(b) easement roads/trails allow public access to otherwise isolated acres of public land or major waterways.

#### Can 17(b) easements be terminated?

Yes, but only the BLM can terminate a 17(b) easement, using the following process. When the BLM or the easement manager determines that an easement is no longer necessary, the BLM must provide public notice that the easement is proposed for termination and request comments from the public. After reviewing the comments and determining the easement is no longer required, the BLM issues an appealable decision terminating the easement. The BLM terminates the public easement when the decision is final by issuing a release of interest.



Some 17(b) road or trail easements have an adjacent site easement designated for changing modes of transportation. Don't block the road or trail easement to off-load an ATV or other equipment.

February 26, 2016

#### General Legal Authorities & Agreements

Section 17(b) of the Alaska Native Claims Settlement Act (ANCSA) of December 18, 1971, 43 U.S.C. 1616 (1b) (authority for reserving public easements)

Federal Land Management Policy Act of 1976 (FLPMA)

Section 903 (a) and (b) of the Alaska National Interest Lands Conservation Act (ANILCA) of December 2. 1980, (adds guiding principles when reserving easements and authorizes the acquisition of easements)

Code of Federal Regulations 43 CFR 2650.4-7 and 2650.0-5 (public easements)

Code of Federal Regulations 43 CFR 4.410 (who can appeal)

Departmental Manual 601 DM 4 (Department of the Interior guidance on administration of Section 17(b) easements)

Memorandum of Understanding (MOU) among the BLM, NPS, and FWS dated 12/12/88 (governs which agency will administer, the process for administering, and the termination of Section 17(b) easements)

MOU between the BLM and the USFS dated 9/4/90 (governs which agency will administer, the process for administering, and the termination of Section 17(b) easements)

There are hundreds of 17(b) easements all over the state. The BLM, FWS, NPS and Native Corporations are striving to mark most of the popular ones with trailhead information and new markers. Leave the markers where they are to help others navigate and avoid trespass.

Cover: Riding along a 17(b) easement near Glennallen



#### Where can I find information on 17(b) easements?

#### Federal Land Agencies

Bureau of Land Management
Alaska State Office
Anchorage District Office
Anchorage Field Office
Gennallen Field Office
Giennallen Field Office
Fairbanks District Office
(907) 822-3217
(907) 474-2251

US Fish and Wildlife Service

Anchorage Division of Realty (907) 786-3490 and Natural Resources 1-888-697-9826 http://ala.ska.fws.gov/nwr/realty/map/ea.sements.htm

National Park Service <a href="https://www.nps.gov/state/ak">www.nps.gov/state/ak</a> Alaska Regional Office <a href="https://www.nps.gov/state/ak">www.nps.gov/state/ak</a>

#### State of Alaska Agencies

Dept. of Fish and Game
Anchorage Office


www.adfg.state.ak.us
(907) 267-2463

Dept. of Natural Resources
Anchorage Office
Fairbanks Office

Mww.dnr.state.ak.us
(907) 269-8400
(907) 451-2705

#### Native Regional Corporations

Ahtna, Inc.	Glennallen, AK (907) 822-3476	www.ahtna-inc.com
Aleut	Anchorage, AK (907) 561-4300	www.aleutcorp.com
Arctic Slope	Anchorage, AK (907) 339-6000	www.asrc.com
Bering Straits	Nome, AK (907) 443-5252	www.beringstraits.com
Bristol Bay	Anchorage, AK (907) 278-3602	www.bbnc.com
Calista	Anchorage, AK (907) 279-5516	www.calistacorp.com
Chugach Alaska	Anchorage, AK (907) 563-8866	www.chugach-ak.com
Cook Inlet (CIRI)	Anchorage, AK (907) 274-8638	www.ciri.com
Doyon, Limited	Fairbanks, AK (907) 459-2000	www.doyon.com
Koniag	Kodiak, AK (907) 486-2530	www.koniag.com
NANA	Kotzebue, AK (907) 442-3301	www.nana.com
Sealaska	Juneau, AK (907) 586-1512	www.sealaska.com





Access to your public lands

http://www.blm.gov/pgdata/etc/medialib/blm/ak/aktest/rec/ 17b.Par.64524.File.dat/17b\_easement\_brochure07.pdf

## Additional 17(b) Easement Resources

### BLM Instruction Memorandum No. AK 2007-037

### Alaska Native Claims Settlement Act Section 17(b) Easement Management

http://www.blm.gov/pgdata/etc/medialib/blm/ak/aktest/ims.Par.6478.File .dat/%20im\_ak\_2007\_037.pdf

### ANCSA 17(b) Easement Management Handbook

http://www.blm.gov/pgdata/etc/medialib/blm/ak/aktest/ims.Par.26550.File.dat/ im\_ak\_2007\_037\_17bhandbook.pdf

## Appendix 1

http://www.blm.gov/pgdata/etc/medialib/blm/ak/aktest/ims.Par.75605.File.dat /im\_ak\_2007\_037\_Appendix1.pdf/

### Appendix 2

http://www.blm.gov/pgdata/etc/medialib/blm/ak/aktest/ims.Par.19605.File.dat /im\_ak\_2007\_037\_Appendix2.pdf

## Alaska Public Easement Defense Fund v. Andrus 435 F. Supp. 664 (D. Alaska 1977

https://www.courtlistener.com/akd/8itv/alaska-public-easement-defensefund-v-andrus/



### ANSCA 17(b) Easements Information

#### WHAT ARE THEY?

The "17(b) Easements" are named after the section of the Federal Regulation, Alaska Native Claims Settlement Act "ANCSA" (PL 92-203 - 85 Stat. 688). This Federal Regulation allows reserving easements on lands which will be conveyed to Alaska Native Village and Regional Corporations in order to allow public access to public land and water. The Federal Regulations, 43 CFR 2650.4-7, describe the guidelines which are used in reserving easements in conveyance documents.

#### HOW CAN EASEMENTS BE USED?

There are different widths of 17(b) trail easements and site easements which allow certain uses. Please note: Departing from these easements on to Native lands without express permission from the Native Land owners is trespass. Please research land status before using these easements and respect the private property rights of the land owners. Below is a list of how you can use each type of easement.

25-Foot Trail - The uses allowed on a 25-foot-wide trail easement are: travel by foot, dogsleds, animals, snowmobiles, two- and three-wheeled vehicles, and small all-terrain vehicles (less than 3,000 lbs. gross vehicle weight).

**50-Foot Trail** - The uses allowed on a 50-foot-wide trail easement are those allowed for a 25-foot trail plus large all-terrain vehicles (more than 3,000 lbs. gross vehicle weight), tracked vehicles, and four-wheel-drive vehicles.

**60-Foot Road** - The uses allowed on a 60-foot-wide road easement are those allowed for 25- and 50-foot trails plus automobiles and trucks.


1-Acre Site - The uses allowed on a site easement are: vehicle parking (e.g., aircraft, boats, all-terrain vehicles, snowmobiles, cars, and trucks), temporary camping, and loading or unloading. Temporary camping, loading, or unloading is limited to 24 hours.

February 26, 2016

http://dnr.alaska.gov/mlw/trails/17b/


Department of Transportation and Public Facilities 2301 Peger Road Fairbanks, Alaska 99709-5316

Dear Mr. Miller:



Pursuant to the Memorandum of Understanding AK020-9701 of October 24, 1996, the Bureau of Land Management has reviewed the status of the easement listed below that provides access to land or water under State administration. Administration of the 17(b) easement is hereby transferred to you.





mhydun

# AHTNA

INCORPORATED

## WELCOME TO KLUTINA LAKE TRAIL

AHTNA, INC. WELCOMES YOU. THIS IS A FEE AREA. DAY USE IS \$5.00 PER PERSON. OVERNIGHT CAMPING IS \$20.00. TRAIL IS A PUBLIC 17(B) EASEMENT THAT ALLOWS FOR VEHICULAR TRAFFIC TO MILE 23. IF YOU WISH TO DRIVE TO MILE 23 THERE IS NOT A CHARGE, HOWEVER IF YOU WISH TO STOP AND CAMP OR FISH, A PERMIT IS REQUIRED. A PERMIT IS REQUIRED FOR CAR OR TRUCK TO TRAVEL BEYOND MILE 23. PLEASE TAKE A PERMIT, FILL IT OUT, PLACE YOUR PAYMENT IN THE ENVELOPE, DETACH THE TOP OF THE PERMIT AND PLACE IT VISIBLY ON THE DASH OF YOUR VEHICLE, AND DEPOSIT THE ENVELOPE IN THE BOX. CAMP HOSTS WILL MAKE DAILY VISITS TO THE AREA TO ASSIST YOU AND TO ENSURE THAT PERMITS HAVE BEEN PAID FOR. PLEASE RESPECT OUR EFFORTS TO MAINTAIN THE BEAUTY OF THE AHTNA REGION.

WE HOPE THAT YOU ENJOY YOUR STAY.

THANK YOU. CHEEN-AN.



February 26, 2016

Klutina Lake Road – Copper Center

## 2002 AGO Opinion: Scope of Klutina Lake Road Right-of-Way

John F. Bennett

A.G. file no: 665-01-0201

July 17, 2002

Page 10

Third, the Department of the Interior recognizes that § 17(b) easements and R.S. 2477 rights-of-way may overlap and that neither easement supplants the other. The Interior Board of Land Appeals has long held that

where "BLM seeks to reserve a sec. 17(b) public easement over an existing road constructed by the State and claimed by the State as an R.S. 2477 right-of-way, the conveyance documents shall contain a provision specifying that the reserved public easement is subject to the claimed R.S. 2477 right-of-way" if valid.

http://www.law.state.ak.us/pdf/opinions/opinions\_2002/ 02-015\_665010201.pdf



### United States Department of the Interior

### BUREAU OF LAND MANAGEMENT ALASKA STATE OFFICE 222 W. 7th Avenue, #13 ANCHORAGE, ALASKA 99513-7599

This letter is in response to your inquiry of November 15, 2002, concerning the civil lawsuit, Ahtna, Inc. v. Hughes, et al., involving use of a section 17(b) easement reserved to the United States.

patent 50-2001-0492 issued to Ahtna, Inc. The U.S. rights are subject to any valid rights the State of Alaska may have under R.S 2477. (See <u>Alaska Department of Transportation</u>, 88 IBLA 106 [1985]).

In summary, the Hughes, as members of the public, have the right to use the Klutina River Road Sec. 17(b) easement to access the Klutina River and offload boats on the road and launch them into the river at those points where the Sec. 17(b) easement abuts State owned lands or at site easement EIN 10a C5. The Hughes cannot use the Sec. 17(b) easement for berry picking or fishing, as these uses were not reserved to the United States.

## November 21, 2002 – BLM State Office

Fishing guide used Klutina Lake Road to access Klutina River without Ahtna permit...Ahtna filed trespass action.

6	IN THE SUPERIOR COURT FOR THE STATE OF ALASKA				
7	THIRD JUDICIAL DISTRICT AT ANCHORAGE				
8					
9	AHTNA INC.,	)			
10	Plaintiff,	)			
11		)			
12	VS.	) Case No			
13	LEON VON SCHEBEN, Commissioner,	Ś			
14	Department of Transportation & Public	)			
15	Facilities, State of Alaska,	)			
16	Defendant.	)			

21. Defendant and those being directed by him, fail and refuse to recognize the ownership and administrative authority of Plaintiff, fail and refuse to provide notice, fail and refuse to comply with land planning requirements, fail and refuse to restrict activities to the confines of the federal § 17(b) easements and the requirements of federal law all of which are contrary to the intend and purpose of ANCSA and the basic land ownership rights of Plaintiff.

April 2, 2008 ~ Ahtna v. Von Scheben RS-2477 vs. ANCSA 17(b)

February 26, 2016

21

22

23

24

25

2. Pursuant to Sec. 17(b) of the Alaska Native Claims Settlement Act of December 18, 1971 (85 Stat. 688, 708; 43 U.S.C. 1601, 1616(b)), the following public

easements, referenced by easement identification number (EIN) on the easement maps attached to this document, copies of which will be found in case file AA-6658-EE, are reserved to the United States. All easements are subject to applicable Federal, State, or Municipal corporation regulation. The following is a listing of uses allowed for each type of easement. Any uses which are not specifically listed are prohibited.

c. (EIN 11 C3, C5, D1, D9, L) An easement sixty (60) feet in width for an existing road from the Copper Center area in Sec. 12, T. 2 N., R. 1 N., Copper River Meridian, southwesterly to site EIN 10a C5, on the Klutina River near Klutina Lake. The uses allowed are those listed above for a sixty (60) foot wide road easement.

Kluti-Kaah Corporation Patent 50-80-0108 Ahtna, Inc. – Klutina Lake Road

#### SENATE BILL NO. 94

#### IN THE LEGISLATURE OF THE STATE OF ALASKA

TWENTY-EIGHTH LEGISLATURE - FIRST SESSION

"An Act vacating a portion of the Copper Center-Valdez right-of-way; and relating to rights-of-way acquired under former 43 U.S.C. 932 that cross land owned by an Alaska Native corporation."

(10) one overlap of an R.S. 2477 right-of-way and 17(b) easement involves a road and all-terrain vehicle trail that roughly parallel the Klutina River from the New Richardson Highway to partway around Klutina Lake; the road and trail form a portion of the

Sec. 19.30.430. Rights-of-way acquired under former 43 U.S.C. 932 that cross land conveyed to a Native corporation. (a) Notwithstanding AS 19.10.015(a), a right-of-way granted under former 43 U.S.C. 932 (R.S. 2477) that crosses land owned by a Native corporation is limited to the uses of the route established on October 21, 1976, and may not exceed a width of 60 feet.

(b) A right-of-way granted under former 43 U.S.C. 932 (R.S. 2477) that crosses land owned by a Native corporation may be used only for transportation purposes and may not be used for rest areas, parking lots, overnight camping, boat launches, recreation sites, or other similar uses.

http://www.legis.state.ak.us/PDF/28/Bills/SB0094A.pdf

February 26, 2016

mhulmhuh

# The End

